

費目・工種・種別	規格	区分	実施設計			変更設計	
			数量	単位	算出式	数量	単位
水道管布設替工事							
水道本管布設替工							
水道管布設替工（A5ｲﾝ）							
管路土工							
【舗装版取壊し工（一次）】							
舗装版切断As	機労	252.0	m	252.00			
舗装版切断Co		2.0	m	2.00			
舗装版直接掘削積込	機労	81.0	m2	81.00			
【殻運搬工】							
As殻運搬4tL=4.0km	機労	4.0	m3	4.00			
Co殻運搬4tL=4.0km	機労	0.1	m3	0.10			
As廃材処理	廃	10.0	t	9.40			
Co廃材処理	廃	0.2	t	0.24			
【土工】							
ﾊﾞｯｸﾙ掘削積込	機労	82.0	m3	82.23			
発生土運搬費4tL=5.0km	機労	99.0	m3	98.68			
残土処分費	廃	99.0	m3	98.68			
管路埋戻費	機労	60.0	m3	60.44			
購入土山砂	材	81.0	m3	80.59			
【舗装工（仮復旧）】							
下層路盤工ARC-40t=150	機労材	80.0	m2	80.00			
下層路盤工ARC-40t=220	機労材	1.0	m2	1.00			
上層路盤工M-40t=120	機労材	80.0	m2	80.00			
仮舗装②粗粒度Ast=30	機労材	81.0	m2	81.00			
【舗装版取壊し工（二次）】							
舗装版切断As	機労	252.0	m	252.00			
舗装版切断Co	機労	2.0	m	2.00			
舗装版直接掘削積込	機労	157.0	m2	157.20			
【殻運搬工】							
As殻運搬4tL=4.0km	機労	6.0	m3	6.21			
Co殻運搬4tL=4.0km	機労	0.1	m3	0.06			
As廃材処理	廃	15.0	t	14.59			
Co廃材処理	廃	0.1	t	0.14			
【舗装工（本復旧工）】							
不陸整正	機労	157.0	m2	157.20			
表層工⑨粗粒度t=50	機労材	156.0	m2	155.60			
Co舗装工t=10cm	機労材	0.2	m3	0.16			

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]